

## **Main Road Mill and Fill**

### **1. Description.**

1.1 Furnish all equipment, labor and materials necessary to execute the project as described below under the direction of the Road Superintendent.

1.2 Mill the full width of Main Rd. 1 ½ or as directed by the Road Superintendent. Millings will be the property of the Town of Tyringham. Contractor shall provide adequate trucks to support continuous milling operations. Dump site will be at the Tyringham Transfer station, 27 Monterey Rd.

1.3 Apply tac coat at a rate of .07 gal. Per sq. yd.

1.4 Apply 2" Hot Mix Asphalt with 3/8" stone approximately 23' wide by 7850' long following the existing profile of the road. Contractor shall provide an adequate number of trucks to support continuous paving operations.

### **2. Materials.**

2.1 Tac Coat applied at a rate of 0.07 Gallons per square yard

2.2 Hot Mix Asphalt with 3/8" stone meeting MassDot specs

### **3. Construction Requirements.**

3.1 All work performed under this contract shall comply with all specifications included herein and with MassDOT Standard Specifications for Highways and Bridges, and Construction and Traffic Standard Details, latest editions. The Town of Tyringham reserves the right to test and sample any materials at any given time for the purpose of quality and workmanship throughout the procedure.

3.2 The Contractor shall be responsible for any cleaning and removal of any loose, deleterious and/or organic matter from the existing surfaces prior to paving

3.3 The finished plane of the road surface must be smooth and free of defects.

3.4 Paving operations shall not be performed when the atmospheric temperature is below 50 degrees Fahrenheit or when the weather is foggy or rainy, or when weather conditions are such that proper paving and compacting of the HMA